

**ANGEL OF THE WINDS CASINO RESORT  
WATER & WASTEWATER FACILITY IMPROVEMENTS**

**ADDENDUM NO. 3 (1 page)  
Issue Date: March 19, 2018**

General: Recitations of each and every section of the bid documents impacted by this addendum are not given. The described changes impact all relevant portions of the bid documents whether specifically cited below or not.

**GENERAL CONTRACT CLARIFICATIONS**

1. Precast Concrete Vaults for WWTP Equalization Basin Area:

Clarification: The valve vault (Sheet M8.1) and flow meter vault (Detail 2, Sheet M9.1) will both need to be similar size (4'-2"L x 4'-2"W x 5'D approx.).

**DRAWINGS**

**Sheet C5.0:**

- Detail 2: Drawing does not indicate that pipe supports are to be removed. Pipe supports can remain in place. If there is any exposed steel on materials that are being left in place, that exposed steel is to be coated per Specifications 13100.

**SPECIFICATIONS**

**Section 11100 – Iron & Manganese Removal System:**

1.05.A.2 - Delete this paragraph.

**Section 13100 – Welded Steel Reservoir Modifications:**

3.01.A. - Clarify that the level of effort for reservoir cleaning includes an expectation that all loose debris and sediment is removed from the reservoirs. It does not include installing scaffolding on the interior of the reservoir and scrubbing / power washing the interior walls.