

**ANGEL OF THE WINDS CASINO RESORT
WATER & WASTEWATER FACILITY IMPROVEMENTS**

**ADDENDUM NO. 4 (2 pages total)
Issue Date: March 19, 2019**

General: Recitations of each and every section of the bid documents impacted by this addendum are not given. The described changes impact all relevant portions of the bid documents whether specifically cited below or not.

SPECIFICATIONS

Division 27 – Process Control and Instrumentation:

See attached Instrumentation Bill of Materials (BOM). These items will be provided by the System Integrator (TSI).

DRAWINGS

SHEET M8.1:

Non-shrink grout is shown on bottom slab of the equalization basin. Grout is called out so that required slope can be achieved. Contractor may use concrete (instead of grout) on slab areas outside of the 6'x5' pump station sump; however, please note that reinforcement must be adjusted so that the maximum unreinforced thickness at the top of the slab section does not exceed 5 inches.

ATTACHMENTS INCLUDED ON FOLLOWING PAGE:

- **Instrumentation BOM**

*****END OF ADDENDUM*****

