

**CITY OF FERNDALE
WATER TREATMENT PLANT UPGRADE**

**ADDENDUM NO. 3 (1 pages total)
Issue Date: September 15, 2023**

General: Recitations of each and every section of the bid documents impacted by this addendum are not given. The described changes impact all relevant portions of the bid documents whether specifically cited below or not.

BID ADVERTISEMENT:

BID OPENING DATE ADJUSTMENT:

The bid opening will be at **1:30 PM on September 27, 2023** (not September 20, 2023).

PART 3 – TECHNICAL SPECIFICATIONS:

SECTION 33 33 00 – HDPE PIPING

2.01 HDPE PIPE

1. **REVISION:** IPS size HDPE pipe is allowed in place of DIPS size HDPE pipe. If IPS size is used, the Contractor shall ensure that change in size does not interfere with installation and operation of the piping.

SECTION 45 05 10 – PRESSURE REDUCING VALVE

- **REVISION:** *Return Flow Feature* is NOT needed for this valve.
- **CHANGE:** Footer Section number should read 45 05 10.

SECTION 45 05 20 – PRESSURE RELIEF/SUSTAINING VALVES

PART 2.01 D-5

- **DELETE:** ~~“The control valve manufacturer shall provide a computerized cavitation analysis report which shows flow rate, differential pressure, and percentage of valve opening. Cv factor, system velocity, and if there will be cavitation damage.”~~

DRAWINGS:

DRAWINGS C2.1, C4.1, C4.2, M1.1, M1.2, M1.7, M1.8, M1.9, M1.10, M1.12, S1.2

DELETE: Unlabeled concrete slab at north edge of Remineralization building.

DRAWING C6.1

REVISION: For all trench drains called out as 8” wide, 6-1/4” wide may be used.

DRAWING M1.9

REVISION: For all trench drains called out as 8” wide, 6-1/4” wide may be used.

REVISION: Key Note 12 pointing to drain pipe should be Key Note 14 (referring to 4” drain pipe).